


CORDOBA STATION 4.8M

CABLE SCHEDULE BETWEEN BUILDING AND ANTENNA (CFE) 6					
PORT NO.	SIZE	DESCRIPTION	TO/FROM	TO/FROM	RESERVED FOR
P1	4"	DOWNLINK COAXIAL CABLES LNA STANDBY/OFFLINE INJECT	BUILDING	ANTENNA	GDST FURNISHED CABLES: • 1/4" DOWNLINK CABLES - 3EA • 1/4" LNA STANDBY/OFFLINE INJECT CABLES - 2EA
P2	4"	LNA CABLES/ CONTROL	BUILDING	ANTENNA	GDST FURNISHED CABLES: • PDU TO ACU RS232/422 - 2EA • LNA CONTROL - 1EA • MRU - 1EA • M&C ETHERNET CABLE - 1EA • HUB TEMP STS/RAIN BLOWER STS - 2EA
P3	4"	SPARE	BUILDING	ANTENNA	
P4	4"	UTILITY AND TECHNICAL AC POWER TO HUB EQUIPMENTS/ LIGHTS / RECEPTACLES/ ANTENNA PDU AC POWER	BUILDING	ANTENNA	ARSAT FURNISHED CABLES: • POWER UP-1 TO ANTENNA INTERFACE J-BOX - 1EA • POWER TP-1 TO ANTENNA INTERFACE J-BOX - 1EA ARSAT FURNISHED CABLES: • POWER UP-1 TO PDU (POWER) - 1EA • POWER TP-1 TO PDU (LOGIC POWER) - 1EA

BUILDING PORTS (CFE)



4" PORT

GENERAL DYNAMICS
SATCOM Technologies, Inc.
SAN JOSE

NOV 10 2011

DOCUMENT CONTROL
RELEASED

SIZE	CAGE CODE	ITEM	SUB-ASSY	TYPE	REV
D	1MA11	7470	34	05	A
SCALE NONE		FN: 7470-34-05_RevA		SHEET 2 OF 2	